



कार्यालय, गाजियाबाद विकास प्राधिकरण, गाजियाबाद।

पत्रांक: 400 / 4 / ई0ई0-ई0 / 2025-26

दिनांक: 01 / 04 / 2026

शुद्धि पत्र

कृपया ई०-निविदा सूचना पत्र संख्या-663 / 4 / पी०ए०-(टी०) / 2025-26 दिनांक 20.03.2026 के तालिका में अंकित क्रमांक संख्या-3 राजनगर एक्सटेंशन क्षेत्र में जी०डी० गोयंका स्कूल के सामने 45 मीटर चौड़ी रोड पर स्ट्रीट लाइट लगाये जाने के कार्य हेतु ई-निविदा में अपलोड की गयी (Percentage Boq) बी०ओ०क्यू० के क्रमांक सं०-1 से 20 पर अंकित यूनिट को बिड डाक्यूमेंट में दर्शित किये गये यूनिट को कन्सीडर किया जाये। क्योंकि (Percentage Boq) बी०ओ०क्यू० के क्रमांक सं०-1 से 19 के यूनिट में त्रुटिवश क्यूबिक मीटर एवं क्रमांक सं०-20 पर Hours ई० निविदा में अपलोड हो गया है। जिससे बिड डाक्यूमेंट में दर्शित किये गये यूनिट के अनुरूप पढ़ा जाये। शेष अन्य नियम व शर्तें यथावत रहेंगी।

भवदीय

अधिशाली अभियन्ता, (वि०/याँ०)
गा०वि०प्रा०, गाजियाबाद।

दिनांक: / / 2025

पृष्ठांकन / / ई०ई०-ई० / 2025-26
प्रतिलिपि:

1. प्रभारी ई-टैण्डर सेल को सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रेषित।

अधिशाली अभियन्ता (वि०/याँ०)
गा०वि०प्रा०, गाजियाबाद।

Percentage BoQ

Tender Inviting Authority: VICE CHAIRMAN GHAZIABAD DEVELOPMENT AUTHORITY						
Name of Work: Installation work of street lights on the 45-meter wide road in Rajnagar Extension area, in front of GD Goenka School.						
Contract No: 663/4/PA-T/2025-26 Dt. 20.03.2026 (S.no-3)						
Name of the Bidder/ Bidding Firm / Company						
PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	Supply & fixing of 9 mtr GI Octagonal Pole of approved make (top dia 100mm, Bottom dia 155 mm and base plate 12mm thick) having 3mm thickness with Double arm bracket (3 Mtr length each) on RCC foundation including the cost of foundation, foundation bolts, excavation & back filling and Required T&P complete in all respect.	50	Nos.	21430.00	1071500.00	INR Ten Lakh Seventy One Thousand Five Hundred & Paise Zero Only
2	1/φ of 63 KVA 11/0.433 KV outdoor type 3 phase conventional 50 C/S aluminium wound Delta/Star DYN 11, ONAN cooled transformer with oil circuit type changer having range +5% to -10% with complete fitting and accessories confirming to IS 11804 Star rating with latest amendments including first filling of oil complete in all respect as per UPPICL Approved make & Specifications as per direction of engineer incharge.	1	Nos.	169341.00	169341.00	INR One Lakh Sixty Nine Thousand Three Hundred Forty One & Paise Zero Only
3	Supply of STP 11M IS-410 SP-55 bottom galvanized complete in all respect.	2	Nos.	16469.00	32938.00	INR Thirty Two Thousand Nine Hundred Thirty Eight & Paise Zero Only
4	Erection of metallic pole of following length in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) foundation including excavation and refilling etc. as required. Above 10.00 meter and upto 12.00 meter. (8177*0.789=6451.65*(111/110)=6510.30)	2	Nos.	6,510.30	13020.60	INR Thirteen Thousand Twenty & Paise Sixty Only
5	Supplying of 50 mm X 8 mm M.S. flat iron pole top bracket/ cross arm for single 11/22/33 KV over head line conductor complete with fixing clamps, bolts, nuts and washers drilling holes for insulator pins, bolts and nuts etc and painting with primer and finish paint as required (615*0.789=485.23*(111/110)=489.64)	5	Nos.	489.64	2448.20	INR Two Thousand Four Hundred Forty Eight & Paise Twenty Only

6	Supplying of two lengths of channel iron 75mm * 40mm * 6mm (7.14 kg per metre) double pole cross arm for three wire 11KV overhead line conductors complete with through bolts and nuts for clamping to the poles, 50mm * 6mm M.S. flats welded on one side to the channel iron and with bolts and nuts on the other side for tying the cross arms together, including drilling holes for insulator pins/fittings, bolts, nuts and washers etc (as per drawing) and painting with primer and finish paint as required. [5125*0.789=4043.625* (111/110)=4080.385]	1	Set	4,080.39	4080.39	INR Four Thousand Eighty & Paise Thirty Nine Only
7	5/Fixing of 11 KV pin insulator with pin including Labour T&P complete in all respect as per direction of E/I.	3	No.	213.00	639.00	INR Six Hundred Thirty Nine & Paise Zero Only
8	X/Fixing of 11 KV TPMO complete in all respect, as per direction by E/I.	1	No.	17,822.00	17822.00	INR Seventeen Thousand Eight Hundred Twenty Two & Paise Zero Only
9	5/Fixing of 11 KV Fuse sets (drop out) with clamps complete in all respect as per direction by E/I.	1	No.	7,027.00	7027.00	INR Seven Thousand Twenty Seven & Paise Zero Only
10	5/Fixing of 11 KV Lighting Arrester set (03 Nos.) complete in respect, as per direction by E/I.	1	No.	1,980.00	1980.00	INR One Thousand Nine Hundred Eighty & Paise Zero Only
11	5/F of 1.54 mtr long 20 mm dia MS Earth Rod with 6 SWG GI earth wire, nut, bolt & washer etc. complete in all respect.	4	nos.	441	1754.00	INR One Thousand Seven Hundred Sixty Four & Paise Zero Only
12	Earthing with G.I. earth pipe 4.5 meter long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal/ coke and salt as required. [6855*0.789=5408.595* (111/110)=5497.764]	12	Nos.	5457.760	65493.12	INR Sixty Five Thousand Four Hundred Ninety Three & Paise Twelve Only
13	Providing and fixing 25 mm X 5 mm G.I. strip in 40 mm dia G.I. pipe from earth electrode including connection with G.I. nut, bolt, spring, washer excavation and re-filling etc. as required. [706*0.789=557.034* (111/110)=562.097]	18	Mtr	562.10	10117.80	INR Ten Thousand One Hundred Seventeen & Paise Eighty Only
14	Providing and fixing 6 SWG dia G.I. wire on surface or in recess for loop earthing as required. [70*0.789=55.23* (111/110)=55.732]	1200	Mtr	55.73	66876.00	INR Sixty Six Thousand Eight Hundred Seventy Six & Paise Zero Only
15	Trenchless boring with HDPE Pipe by Machine Technology including Labour, T&P, cost of Pipe and all required material suitable for laying of LT upto 95 Sqmm size with proper completion of work as per direction of E/I.	150	Mtr	882.00	132300.00	INR One Lakh Thirty Two Thousand Three Hundred & Paise Zero Only
16	Supplying and laying of following size DWC HDPE pipe (S) marked along with all accessories like socket, bend, couplers etc. conforming to IS 14940, Part II complete with fitting and cutting, jointing etc. direct in ground (75 cm below ground level) including excavation and refilling the trench but excluding sand cushioning and protective covering etc., complete as required. 63mm Dia (OD-63mm & ID-51 mm nominal) [247*0.789=194.89* (111/110)=196.65]	1000	Mtr	195.65	195650.00	INR One Lakh Ninety Five Thousand Six Hundred Fifty & Paise Zero Only

17	Supply and laying of aluminium conductor PVC insulated armoured served sheathed cables 1100 Volts grade at a depth of 750 mm below ground level over a cushion of 75 mm. thick sand all around and protected with burnt bricks on sides and on top. On surface the cable run shall be fixed on M.S. clamps etc. of suitable size or as directed by the Engineer. Incharge complete in all respect. The armouring of the cable shall be properly connected with the earth conductor by clamps etc. <u>Size: 25 sq.mm 3-1/2 core</u>	1500	Mtr	373.00	559500.00	INR Five Lakh Fifty Nine Thousand Five Hundred & Paise Zero Only
18	<u>Street Light work:</u> Supply and fixing of LED Street light Fitting having die cast aluminium body and diffuser with driver set suitable for 110 to 130 Watt. Conforming to IP 66 Protection complete in all respect. CAT-AAA	105	Nos.	10500.00	1102500.00	INR Eleven Lakh Two Thousand Five Hundred & Paise Zero Only
19	Supply and fixing 40 A TPN capacity of automatic street light cubicle control panel painted with anti corrosive alkali and acid proof paint consisting of time switch TSO 100 series with contactors, HRC fuses, isolating switch metering instrument & instrument box with CTs etc. in case of TPN, complete in all respect.	1	Nos.	29300.00	29300.00	INR Twenty Nine Thousand Three Hundred & Paise Zero Only
20	S/L of 10 Sqmm x 2 core Unarmoured LT 1100 Volt Aluminium Conductor twin Rate cable Complete.	1000	Mtr.	74.00	74000.00	INR Seventy Four Thousand & Paise Zero Only
Total in Figures					3558297.11	INR Thirty Five Lakh Fifty Eight Thousand Two Hundred Ninety Seven & Paise Eleven Only
Quoted Rate in Figures			Select		0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only				